





































































CTH CE EARTHWORK						
Station	Fill Area (SF)	Cut Area (SF)	Fill Volume (CY)	Cut Volume (CY)	Cumulative Fill Vol (CY)	Cumulative Cut (CY)
3+00.00	0.00	0.00	0.00	0.00	0.00	0.00
3+25.00	0.00	0.00	0.00	0.00	0.00	0.00
3+50.00	0.00	0.00	0.00	0.00	0.00	0.00
3+75.00	0.00	0.00	0.00	0.00	0.00	0.00
4+00.00	0.00	0.00	0.00	0.00	0.00	0.00
4+25.00	0.00	0.00	0.00	0.00	0.00	0.00
4+50.00	0.25	41.82	0.12	19.36	0.12	19.36
4+75.00	0.35	43.13	0.28	39.33	0.40	58.69
5+00.00	0.41	41.20	0.35	39.04	0.75	97.73
5+25.00	1.92	42.86	1.08	38.91	1.82	136.64
5+50.00	1.86	41.28	1.75	38.95	3.58	175.59
5+75.00	2.53	41.57	2.03	38.35	5.61	213.95
6+00.00	4.44	40.11	3.22	37.81	8.83	251.76
6+25.00	6.07	39.96	4.86	37.07	13.69	288.83
6+50.00	7.31	38.49	6.19	36.32	19.88	325.15
6+75.00	7.79	39.58	6.99	36.14	26.87	361.29
7+00.00	0.24	42.93	3.72	38.20	30.59	399.49
7+25.00	0.40	45.56	0.30	40.97	30.89	440.46
7+50.00	0.69	46.78	0.51	42.75	31.40	483.21
7+75.00	0.66	50.14	0.63	44.87	32.02	528.08

CTH CE EARTHWORK						
Station	Fill Area (SF)	Cut Area (SF)	Fill Volume (CY)	Cut Volume (CY)	Cumulative Fill Vol (CY)	Cumulative Cut (CY)
8+00.00	0.57	49.87	0.57	46.30	32.59	574.38
8+25.00	13.15	56.67	6.35	49.32	38.94	623.70
8+50.00	24.35	47.71	17.36	48.32	56.30	672.03
8+75.00	28.42	40.30	24.43	40.74	80.73	712.77
9+00.00	31.48	40.46	27.73	37.39	108.46	750.15
9+25.00	34.14	44.33	30.38	39.25	138.84	789.41
9+50.00	0.00	93.90	15.81	63.99	154.65	853.40
9+75.00	0.00	90.12	0.00	85.19	154.65	938.59
10+00.00	0.00	94.54	0.00	85.49	154.65	1024.08
10+25.00	0.00	100.58	0.00	90.33	154.65	1114.41
10+50.00	0.00	99.71	0.00	92.73	154.65	1207.14
10+75.00	5.24	103.24	2.43	93.96	157.07	1301.09
11+00.00	53.38	119.85	27.14	103.28	184.21	1404.37
11+25.00	53.87	124.08	49.65	112.93	233.86	1517.30
11+50.00	48.53	132.04	47.40	118.57	281.27	1635.87
11+75.00	44.33	137.41	42.99	124.74	324.26	1760.62
12+00.00	44.97	138.62	41.34	127.79	365.60	1888.41
12+25.00	77.73	138.99	56.80	128.52	422.41	2016.93
12+50.00	47.32	141.29	57.89	129.76	480.30	2146.69
12+75.00	46.22	139.58	43.30	130.03	523.60	2276.73

CTH CE EARTHWORK						
Station	Fill Area (SF)	Cut Area (SF)	Fill Volume (CY)	Cut Volume (CY)	Cumulative Fill Vol (CY)	Cumulative Cut (CY)
13+00.00	36.37	139.53	38.23	129.22	561.84	2405.95
13+25.00	39.76	138.76	35.25	128.84	597.08	2534.78
13+50.00	37.06	142.91	35.57	130.40	632.65	2665.18
13+75.00	36.08	148.03	33.87	134.70	666.52	2799.88
14+00.00	28.62	155.10	29.96	140.34	696.47	2940.22
14+25.00	30.87	148.88	27.54	140.74	724.02	3080.96
14+49.98	30.03	140.37	28.17	133.80	752.19	3214.76
14+75.00	29.52	135.25	27.59	127.70	779.78	3342.46
15+00.00	24.69	131.31	25.10	123.41	804.88	3465.87
15+25.00	29.22	120.47	24.96	116.57	829.84	3582.44
15+50.00	32.30	114.30	28.48	108.69	858.32	3691.13
15+75.00	34.60	111.76	30.97	104.65	889.29	3795.79
16+00.00	28.95	110.39	29.42	102.84	918.71	3898.63
16+25.00	32.34	107.98	28.37	101.10	947.08	3999.73
16+50.00	27.91	108.81	27.89	100.37	974.98	4100.09
16+75.00	26.67	118.87	25.27	105.45	1000.24	4205.55
17+00.00	20.56	127.34	21.87	114.03	1022.11	4319.58
17+25.00	11.00	135.25	14.61	121.57	1036.72	4441.15
17+50.00	6.60	126.25	8.15	121.07	1044.87	4562.21
17+75.00	0.00	188.45	3.06	145.70	1047.93	4707.91

CTH CE EARTHWORK						
Station	Fill Area (SF)	Cut Area (SF)	Fill Volume (CY)	Cut Volume (CY)	Cumulative Fill Vol (CY)	Cumulative Cut (CY)
18+00.00	2.46	133.46	1.14	149.03	1049.07	4856.94
18+25.00	17.62	107.57	9.30	111.59	1058.36	4968.52
18+50.00	16.01	113.58	15.57	102.39	1073.93	5070.91
18+75.00	15.03	109.90	14.37	103.47	1088.31	5174.38
19+00.00	10.54	111.31	11.84	102.42	1100.15	5276.79
19+25.00	13.91	114.18	11.32	104.40	1111.46	5381.19
19+50.00	4.81	132.00	8.67	113.97	1120.13	5495.16
19+75.00	5.78	132.72	4.90	122.56	1125.03	5617.72
20+00.00	5.33	131.22	5.15	122.20	1130.18	5739.91
20+25.00	8.32	123.44	6.32	117.90	1136.50	5857.81
20+50.00	12.19	115.23	9.49	110.49	1145.99	5968.31
20+75.00	17.53	109.70	13.76	104.14	1159.75	6072.44
21+00.00	19.41	173.61				

CTH CE EARTHWORK						
Station	Fill Area (SF)	Cut Area (SF)	Fill Volume (CY)	Cut Volume (CY)	Cumulative Fill Vol (CY)	Cumulative Cut (CY)
33+00.00	13.84	199.46	8.67	186.97	4840.79	12897.21
33+25.00	25.90	155.44	18.40	164.31	4859.19	13061.52
33+50.00	28.92	139.64	25.38	136.62	4884.57	13198.14
33+75.00	41.91	122.33	32.79	121.28	4917.36	13319.42
34+00.00	44.35	115.45	39.93	110.08	4957.30	13429.50
34+25.00	42.26	100.12	40.10	99.80	4997.39	13529.30
34+50.00	37.77	89.15	37.05	87.63	5034.44	13616.93
34+75.00	37.18	83.54	34.70	79.95	5069.14	13696.88
35+00.00	33.51	80.55	32.72	75.97	5101.86	13772.84
35+25.00	36.38	64.75	32.36	67.27	5134.22	13840.11
35+50.00	40.95	61.12	35.80	58.27	5170.02	13898.38
35+75.00	43.30	64.04	39.01	57.95	5209.03	13956.33
36+00.00	32.03	79.69	34.88	66.54	5243.91	14022.87
36+25.00	24.01	87.92	25.95	77.60	5269.85	14100.47
36+50.00	18.45	97.04	19.66	85.63	5289.51	14186.10
36+75.00	16.15	104.81	16.02	93.45	5305.53	14279.55
37+00.00	18.00	117.58	15.81	102.96	5321.34	14382.51
37+25.00	58.18	124.52	35.27	112.08	5356.61	14494.59
37+50.00	1.83	110.78	27.79	108.93	5384.39	14603.53
37+75.00	0.00	121.47	0.85	107.52	5385.24	14711.05

CTH CE EARTHWORK						
Station	Fill Area (SF)	Cut Area (SF)	Fill Volume (CY)	Cut Volume (CY)	Cumulative Fill Vol (CY)	Cumulative Cut (CY)
38+00.00	0.00	115.65	0.00	109.78	5385.24	14820.83
38+25.00	0.00	103.67	0.00	101.53	5385.24	14922.36
38+50.00	1.10	86.40	0.51	87.99	5385.75	15010.36
38+75.00	5.21	113.06	2.92	92.34	5388.67	15102.70
39+00.00	5.52	119.14	4.97	107.50	5393.64	15210.20
39+25.00	7.45	108.83	6.00	105.54	5399.64	15315.74
39+50.00	9.16	102.86	7.69	98.00	5407.33	15413.74
39+75.00	7.63	108.49	7.77	97.85	5415.10	15511.59
40+00.00	6.23	108.78	6.41	100.59	5421.51	15612.17
40+25.00	10.04	102.69	7.53	97.90	5429.04	15710.08
40+50.00	8.67	102.09	8.66	94.81	5437.70	15804.88
40+75.00	4.16	102.51	5.94	94.72	5443.64	15899.60
41+00.00	3.45	102.79	3.53	95.05	5447.17	15994.65
41+25.00	0.75	99.85	1.94	93.82	5449.11	16088.47
41+50.00	0.00	95.50	0.35	90.44	5449.46	16178.91
41+75.00	0.00	89.09	0.00	85.45	5449.46	16264.37
42+00.00	0.00	79.45	0.00	78.03	5449.46	16342.39
42+25.00	0.00	0.00	0.00	36.78	5449.46	16379.18
42+50.00	0.00	0.00	0.00	0.00	5449.46	16379.18
42+75.00	0.00	0.00	0.00	0.00	5449.46	16379.18

CTH CE EARTHWORK						
Station	Fill Area (SF)	Cut Area (SF)	Fill Volume (CY)	Cut Volume (CY)	Cumulative Fill Vol (CY)	Cumulative Cut (CY)
38+00.00	0.00	115.65	0.00	109.78	5385.24	14820.83
38+25.00	0.00	103.67	0.00	101.53	5385.24	14922.36
38+50.00	1.10	86.40	0.51	87.99	5385.75	15010.36
38+75.00	5.21	113.06	2.92	92.34	5388.67	15102.70
39+00.00	5.52	119.14	4.97	107.50	5393.64	15210.20
39+25.00	7.45	108.83	6.00	105.54	5399.64	15315.74
39+50.00	9.16	102.86	7.69	98.00	5407.33	15413.74
39+75.00	7.63	108.49	7.77	97.85	5415.10	15511.59
40+00.00	6.23	108.78	6.41	100.59	5421.51	15612.17
40+25.00	10.04	102.69	7.53	97.90	5429.04	15710.08
40+50.00	8.67	102.09	8.66	94.81	5437.70	15804.88
40+75.00	4.16	102.51	5.94	94.72	5443.64	15899.60
41+00.00	3.45	102.79	3.53	95.05	5447.17	15994.65
41+25.00	0.75	99.85	1.94	93.82	5449.11	16088.47
41+50.00	0.00	95.50	0.35	90.44	5449.46	16178.91
41+75.00	0.00	89.09	0.00	85.45	5449.46	16264.37
42+00.00	0.00	79.45	0.00	78.03	5449.46	16342.39

LODERBAUER ROAD EARTHWORK						
Station	Fill Area (SF)	Cut Area (SF)	Fill Volume (CY)	Cut Volume (CY)	Cumulative Fill Vol (CY)	Cumulative Cut (CY)
101+15.00	0.00	0.00	0.00	0.00	0.00	0.00
101+25.00	0.00	0.00	0.00	0.00	0.00	0.00
101+50.00	0.00	0.00	0.00	0.00	0.00	0.00
101+75.00	0.00	0.00	0.00	0.00	0.00	0.00
102+00.00	0.00	0.00	0.00	0.00	0.00	0.00
102+14.09	0.00	0.00	0.00	0.00	0.00	0.00
103+60.00	0.00	177.04	0.00	479.09	0.00	479.09
103+75.00	0.00	160.44	0.00	93.74	0.00	572.83
104+00.00	0.00	158.95	0.00	147.87	0.00	720.70
104+25.00	0.00	148.34	0.00	142.26	0.00	862.96
104+50.00	0.00	133.01	0.00	130.32	0.00	993.28
104+75.00	0.00	120.10	0.00	117.03	0.00	1110.32
105+00.00	0.00	104.17	0.00	103.71	0.00	1214.03

XS 36

CE TRAIL AND HIGHWAY IMPROV