

SUMMARY OF QUANTITIES OF MAJOR ITEMS- BASE BID

Item NUMBER	ITEM DESCRIPTION	TOTAL ESTIMATED QUANTITY	UNITS	AS-BUILT
205.0100	Excavation Common	4067	CY	
305.0110	Base Aggregate Dense 3/4-Inch	40	TON	
305.0120	Base Aggregate Dense 1 1/4-Inch	5410	TON	
311.0110	Breaker Run	860	TON	
455.0605	Tack Coat	668	GAL	
460.2000	Incentive Density HMA Pavement	1230	DOL	
460.5224	HMA Pavement 4 LT 58-28 S	1097	TON	
460.5225	HMA Pavement 5 LT 58-28 S	823	TON	
619.1000	Mobilization	1	EACH	
624.0100	Water	33	MGAL	
625.0500	Salvaged Topsoil	220	SY	
628.1504	Silt Fence	1103	LF	
628.1520	Silt Fence Maintenance	1103	LF	
628.1905	Mobilizations Erosion Control	1	EACH	
628.1910	Mobilizations Emergency Erosion Control	1	EACH	
628.2006	Erosion Mat Urban Class I Type A	220	SY	
630.0140	Seeding Mixture No. 40	4	LB	
630.0200	Seeding Temporary	6	LB	
630.0500	Seed water	5	MGAL	
638.2102	Moving Signs Type II	1	EACH	
638.3000	Removing Small Sign Supports	1	EACH	
643.0300	Traffic Control Drums	760	DAY	
643.0420	Traffic Control Barricades Type III	114	DAY	
646.8305	Marking Parking Stall Paint	5460	LF	
652.0210	Conduit Rigid Nonmetallic Schedule 40 1-Inch	705	LF	
652.0220	Conduit Rigid Nonmetallic Schedule 40 1 1/2-Inch	405	LF	
652.0225	Conduit Rigid Nonmetallic Schedule 40 2-Inch	1330	LF	
652.0605	Conduit Special 2-Inch	380	LF	
655.0620	Electrical wire Lighting 8 AWG	4084	LF	
655.0630	Electrical wire Lighting 4 AWG	1136	LF	
690.0150	Sawing Asphalt	598	LF	
SPV.0060.01	Adjusting water valve Boxes	1	EACH	
SPV.0060.04	Precast Concrete wheel Stops	30	EACH	
SPV.0060.06	Sign Supports 2x2-Inch 14-FT	1	EACH	
SPV.0060.08	Concrete Bollard	14	EACH	
SPV.0060.09	Concrete Barricade Special	2	EACH	
SPV.0060.12	Concrete Bases with Junction Box	2	EACH	
SPV.0060.13	Lighting Units, Type P6	2	EACH	
SPV.0060.15	Concrete Handholes	11	EACH	
SPV.0060.18	Electrically Operated Barrier Gates	2	EACH	
SPV.0075.01	Street Sweeping	15	HRS	
SPV.0105.02	Metering and Panelboard Equipment	1	LS	
SPV.0105	Conduit Locating	1	LS	

PROJECT NO:

ATW PARKING LOT 2021

COUNTY: OUTAGAMIE

SUMMARY OF QUANTITIES

Addendum 2
Revised Sheet 2

E

SUMMARY OF QUANTITIES OF MAJOR ITEMS- ALTERNATIVE 2

Item NUMBER	ITEM DESCRIPTION	TOTAL ESTIMATED QUANTITY	UNITS	AS-BUILT
205.0100	Excavation Common	4001	CY	
305.0110	Base Aggregate Dense 3/4-Inch	40	TON	
305.0120	Base Aggregate Dense 1 1/4-Inch	5330	TON	
311.0110	Breaker Run	850	TON	
455.0605	Tack Coat	663	GAL	
460.2000	Incentive Density HMA Pavement	1220	DOL	
460.5224	HMA Pavement 4 LT 58-28 S	1089	TON	
460.5225	HMA Pavement 5 LT 58-28 S	816	TON	
619.1000	Mobilization	1	EACH	
624.0100	Water	32	MGAL	
625.0500	Salvaged Topsoil	230	SY	
628.2006	Erosion Mat Urban Class I Type A	230	SY	
630.0140	Seeding Mixture No. 40	4	LB	
630.0200	Seeding Temporary	6	LB	
630.0500	Seed Water	5	MGAL	
643.0300	Traffic Control Drums	760	DAY	
643.0420	Traffic Control Barricades Type III	114	DAY	
646.8305	Marking Parking Stall Paint	5277	LF	
652.0210	Conduit Rigid Nonmetallic Schedule 40 1-Inch	520	LF	
652.0220	Conduit Rigid Nonmetallic Schedule 40 1 1/2-Inch	240	LF	
652.0225	Conduit Rigid Nonmetallic Schedule 40 2-Inch	375	LF	
655.0615	Electrical wire Lighting 10 AWG	370	LF	
655.0630	Electrical wire Lighting 4 AWG	1024	LF	
690.0150	Sawing Asphalt	360	LF	
SPV.0060.04	Precast Concrete wheel Stops	30	EACH	
SPV.0060.09	Concrete Barricade Special	1	EACH	
SPV.0060.12	Concrete Bases with Junction Box	1	EACH	
SPV.0060.13	Lighting Units, Type P6	1	EACH	
SPV.0060.18	Electrically Operated Barrier Gates	1	EACH	
SPV.0075.01	Street Sweeping	15	HRS	

SUMMARY OF QUANTITIES OF MAJOR ITEMS- ALTERNATIVE 3

Item NUMBER	ITEM DESCRIPTION	TOTAL ESTIMATED QUANTITY	UNITS	AS-BUILT
204.0115	Removing Asphaltic Surface Butt Joints	827	SY	
305.0110	Base Aggregate Dense 3/4-Inch	10	TON	
455.0605	Tack Coat	122	GAL	
460.2000	Incentive Density HMA Pavement	340	DOL	
460.5225	HMA Pavement 5 LT 58-28 S	526	TON	
619.1000	Mobilization	1	EACH	
643.0300	Traffic Control Drums	58	DAY	
643.0420	Traffic Control Barricades Type III	4	DAY	
646.8305	Marking Parking Stall Paint	3234	LF	
SPV.0060.19	Salvage Concrete wheel Stops	38	EACH	